

- NOTES:
- ALL DIMENSIONS SHOWN IN TABLE ARE IN INCHES, UNLESS OTHERWISE NOTED & ARE ± 1 INCH (25MM).
 - ALL ITEMS SHOWN IN PHANTOM LINE ARE TO BE PROVIDED BY OTHERS.
 - ALL DIMENSIONS ARE SUBJECT TO CHANGE WITHOUT ANY NOTICE.
 - INSTALL UNIONS FITTINGS ON INLET, OUTLET & DRAIN PLUMBING CONNECTIONS.
 - PROVIDE A 2 FEET MINIMUM CLEARANCE ABOVE MINERAL TANK FOR FILLING MEDIA.
 - A GFCI EQUIPT ELECTRICAL OUTLET SHOULD BE PROVIDED WITHIN 5 FEET OF EQUIPMENT LOCATION.
 - USE DIELECTRIC UNIONS ON PLUMBING CONNECTIONS OF CONTROL VALVE WHEN DISSIMILAR METALS ARE PRESENT.
 - PROVIDED SYSTEM SHALL NOT BE SUBJECT TO ANY VACUUM. IF RISK OF VACUUM IS PRESENT, INSTALL SIPHON BREAK ON DRAIN LINE & INSTALL VACUUM RELIEF VALVE WATTS ORDERING CODE # 0556031 ON INLET LINE.
 - BRINE TANK DIMENSIONS SHOWN ON TABLE ARE FACTORY SELECTED FOR USE WITH THE SPECIFIED SYSTEM SIZE.
 - DO NOT INSTALL DRAIN LINE DIRECTLY TO A DRAIN. FOR PROPER DRAIN CONNECTION FOLLOW ALL NATIONAL, STATE AND LOCAL CODES. DO NOT CONSTRUCT DRAIN LINE TO ELEVATIONS THAT EXCEED 4 FEET ABOVE THE CONTROL VALVE'S DRAIN PORT.
 - THE FULL WEIGHT OF THE PIPING AND VALVES MUST BE SUPPORTED BY PIPE HANGERS OR OTHER MEANS.
 - INLET AND OUTLET HEADERS NEED TO BE SIZED ACCORDING TO FLOW RATE REQUIREMENTS BY OTHERS.
 - POWER REQUIREMENTS: 115V/60HZ 2.7 AMPS PER CONTROL VALVE UNLESS OTHERWISE SPECIFIED.
 - BRINE TANK MUST BE LOCATED WITHIN 10 FEET OF SYSTEM CONTROL VALVE AND ON A COMMON FLOOR ELEVATION WITH MINERAL TANK TO ENSURE PROPER BRINE DRAW OPERATION.
 - USE FACTORY SUPPLIED BRINE TUBING. DO NOT USE SMALLER DIAMETER TUBING THAN WHAT IS SUPPLIED.
 - LIMIT INLET PRESSURE TO NOT EXCEED MAXIMUM PUBLISHED OPERATING PRESSURE.

SERIES HCP-200 DUPLEX PROGRESSIVE DIMENSION (INCHES) & SPECIFICATIONS																		
MODEL NO.	ORDERING CODES (EDP NO.)	MINERAL TANK SIZE	INLET	OUTLET	OVERALL HEIGHT (SEE NOTE 5)	OVERALL DEPTH	OVERALL WIDTH	MINIMUM INLET PIPE DISTANCE	BRINE TANK (SEE NOTE 9)	CONTROL VALVE INLET/OUTLET PIPE SIZE (NPT)	DRAIN CONN. SIZE (NPT)	SERVICE FLOW GPM @ 15 PSI DROP	PEAK SERVICE FLOW GPM @ 25 PSI DROP	DRAIN FLOW RATE (GPM)	MIN/MAX OPERATING TEMP F°	MIN/MAX OPERATING PRESSURE (PSI)	ESTIMATED OPERATING WEIGHT (LBS)	ESTIMATED SHIPPING WEIGHT (LBS)
M4043TI-NH	68110194	14 X 65	67.38	67.38	77.13	16	55	3.5	18 X 40	2.0	1.0	50	80	5.0	34/110	25/125	1903	530
M4047TI-NH	68110195	16 X 65	67.75	67.75	77.88	17	57	5.5	18 X 40	2.0	1.0	70	110	7.0	34/110	25/125	2239	700
M4048TI-NH	68110196	18 X 65	68.5	68.5	78.94	18.13	59	7.5	24 X 41	2.0	1.0	114	130	10.0	34/110	25/125	2962	800
M4052TI-NH	68105422	21 X 62	70.5	70.5	80.94	21.13	62	10.5	24 X 50	2.0	1.0	240	154	12.0	34/110	25/125	4087	1200
M4058TI-NH	68105437	24 X 72	76.75	76.75	87.13	24.13	65	13.5	30 X 50	2.0	1.0	120	194	15.0	34/110	25/125	5993	1420
M4059TI-NH	68105450	30 X 72	80.25	80.25	93.13	30.13	73	16.5	39 X 48	2.0	1.0	160	200	25.0	34/110	25/125	9434	2320
M4060TI-NH	68105462	36 X 72	86	86	97.44	36.13	85	22.5	39 X 60	2.0	1.5	168	210	35.0	34/110	25/125	12411	3120

WATTS
815 CHESTNUT ST.
NORTH ANDOVER, MA 01845

THIS DRAWING IS UNLESS SPECIFIED
LIMITS UNLESS SPECIFIED

FRACTIONAL ANGULAR
1/16" 3/32"
DECIMAL INCHES
3/32" X 1/16" 1/8" X 1/8"
3/16" X 1/8" 1/4" X 1/4"
COMMON ANGLES
15° 30° 45° 60° 75° 90°
SURFACE FINISH
125 R.M.S.
250 R.M.S.
DO NOT SCALE DRAWING

TITLE: GENERAL INSTALLATION, SERIES HCP-200
DUPLEX PROGRESSIVE 2" WATER SOFTENERS

MATERIAL: N/A

OTHER: ESTIMATED WEIGHT: SEE TABLE






PART NO.: SEE TABLE

EDP NO.: SEE TABLE

FILE TYPE: CAD

SIZE: D

REV: 1



CLIENT PROJECT SIGN-OFF	
JOB NAME:	
JOB LOCATION:	
CONTRACTOR:	
CONTRACTOR APPROVAL:	
CONTRACTOR APPROVAL DATE:	
CONTRACTOR PO NO:	
ENGINEER:	
ENGINEER APPROVAL:	
ENGINEER APPROVAL DATE:	